

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 19
DIAGRAM

History of original corner establishment:

The original corner was established by Everett A. Thatcher on August 30, 1879, under GLO contract No. 325, as follows:

Set a stone, 13" x 9" x 9", for 1/4 section corner, from which:



A 10" pine bears N40° E, 42 links (27.72 feet).

A 8" pine bears S40° W, 12 links (7.92 feet).

Original corner evidence recovered:

The original corner stone is gone. The area has been badly disturbed by logging activities. Found the original bearing trees as follows:

A live and vigorous 27" Ponderosa Pine with healed blaze bears N40° E, 27.7 feet.

A 24" sawn Ponderosa Pine stump with lower portion of a healed blaze bears S40° W, 7.9 feet.

Monument and accessories established to perpetuate the original position of this corner:

At the corner point as determined by reference from the original bearing tree evidence, I set a 1" x 30" flared, galvanized iron pipe 23" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I build a mound of stones around the pipe, from which:

A 8" Ponderosa Pine, scribed "1/4 S35 BT", bears S66° E, 26.9 feet.

A 10" Ponderosa Pine, scribed "1/4 S35 BT", bears S43° W, 41.3 feet.

A 8" Ponderosa Pine, scribed "1/4 S26 BT", bears N19° W, 21.5 feet.

Each of the new bearing trees is scribed on double blazes and has a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

I hereby certify the above corner point was perpetuated as hereon described on May 5, 2003. Magnetic declination set in compass: 17° E.

NAD '83 UTM Zone 11 position: 4997077N 290082E (plus or minus two meters).


Dennis L. Gaylord

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY
Morrow County Surveyor

Date: 1-4-2014
Rec'd By: S.K.H
No.: 55 25 V19
Folder No.: _____