

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 25  
DIAGRAM

History of original corner establishment:

The original corner was established by Everett A. Thatcher in August, 1879, under GLO contract No. 325, as follows:

Set a stone, 16" x 12" x 10", for corner to sections 30, 31, 25 and 36. Raised a mound of stone at corner, from which:

A house bears S80° W, 220 links (145.20 feet).

Original corner evidence recovered:

Found the original corner stone solidly set 8" in the ground in a small mound of stones. The corner stone is 14" x 9" x 5" and is plainly marked "5/25" on the narrow, west face. The house referred to above is gone, but there is evidence a house once stood at the position referenced.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 25" into the ground. I bury the corner stone to the east of, and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

A 15" Ponderosa Pine, scribed "T5S R26E S30 BT", bears N20° E, 60.9 feet.

A 10" Ponderosa Pine, scribed "T5S R26E S31 BT", bears S57° 30' E, 145.7 feet.

A 10" Ponderosa Pine, scribed "T5S R25E S36 BT", bears S70° 30' W, 138.8 feet.

A 12" Ponderosa Pine, scribed "T5S R25E S25 BT", bears N5° 30' W, 72.5 feet.

The new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

I hereby certify the above corner was perpetuated as hereon described on May 9, 2003. Magnetic declination set in compass: 17° E.

NAD '83 UTM Zone 11 position: 4996994N 292508E (plus or minus two meters).



Renews June 30, 2003

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on

**RECEIVED BY**  
Morrow County Surveyor

Date: 1-4-2014

Rec'd By: S.K.H.

No.: 5525 V25

Folder No.: \_\_\_\_\_