

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 17 1/2  
DIAGRAM

T5S R25E
S35
A.P.
T6S
PLS 1636
2003

History of original corner establishment:

The original position was established by Everett A. Thatcher while establishing the first standard parallel south, on August 13, 1879, under GLO contract No. 325, as follows:

At 4.70 chains east of the standard corner to sections 34 and 35, "A Pine 30" in diameter". At 4.80 chains east of the same corner, "A Spring, SE".

Original corner evidence recovered:

Found the original line tree, a large Ponderosa Pine, wind thrown and decayed. I was not able to see axe marks on this tree. This position, however, fits the record position east from the section corner to sections 34 and 35, as well as a small ravine to the east of the line tree, fed by a spring a short distance to the north of the standard parallel line.

Monument and accessories established to perpetuate the original position of this corner:

In the center of the root hole where the line tree stood, I set a 1" x 30" flared, galvanized iron pipe 25" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I build a mound of stones around the pipe, from which:

A 13" Ponderosa Pine, scribed "AP BT", bears N54° 30' E, 102.2 feet.

A 23" Ponderosa Pine, scribed "AP BT", bears S55° W, 45.6 feet.

The bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

I hereby certify this corner point was perpetuated as hereon described on May 28, 2003. Magnetic declination set in compass: 17° E.

NAD '83 UTM Zone 11 position: 4995490N 289303E (plus or minus two meters).



Renews June 30, 2003

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY  
Morrow County Surveyor

Date: 1-4-14  
Rec'd By: S. K. H  
No.: 5525 & 17.5  
Folder No.: \_\_\_\_\_