


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 17
DIAGRAM

History of original corner establishment:

The original corner was established by Everett A. Thatcher, while establishing the first standard parallel south, on August 13, 1879, under GLO contract No. 325, as follows:

Set a stone, 14" x 12" x 8", for standard corner to sections 34 and 35. Raised a stone mound at the corner.



Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 14" x 10" x 6" and is marked with four grooves on one face and two grooves on the opposite face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 24" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

- A 16" Ponderosa Pine, scribed "T5S R25E S35 SC BT", bears N81° 30' E, 21.7 feet.
 - A 16" Ponderosa Pine, scribed "T6S BT", bears S8° E, 33.2 feet.
 - A 19" Ponderosa Pine, scribed "S1 BT", bears S8° W, 42.5 feet.
 - A 11" Ponderosa Pine, scribed "T5S R25E S34 SC BT", bears N3° 30' W, 56.1 feet.
 - A wire fence projecting east and west bears south, 1.0 foot.
- The bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

I hereby certify this corner point was perpetuated as hereon described on May 28, 2003. Magnetic declination set in compass: 17° E. NAD '83 UTM Zone 11 position: 4995493N 289208E (plus or minus two meters).

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Dennis L. Gaylord

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY
Morrow County Surveyor

Date: 1-4-2014
Recd By: S.K.H.
No.: 55 25 217
Folder No.: _____