

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 21
DIAGRAM

History of original corner establishment:

The original corner was established by Everett A. Thatcher on August 13, 1879, under GLO contract No. 325 to survey the first standard parallel south, as follows:

Set a stone, 18" x 10" x 6", for section corner to sections 35 and 36, and raised a mound of stone, from which:

A 30" pine bears N78°W, 19 links (12.54 feet).
A 32" pine bears N8°E, 47 links (31.02 feet).

Original corner evidence found:

The corner stone is gone. The corner point falls in a logging skid trail, which has been badly disturbed.

A large, windthrown and decayed Ponderosa Pine with fragmentary scribes visible on double blazes, bears N8°E, 31.0 feet.

A decayed Ponderosa Pine root wad, no marks remaining, root hole bears N78°W, 12.5 feet.

Monument and accessories established to perpetuate the original position of this corner:

At record bearing and distance from the bearing tree evidence, I set a 1" x 30" galvanized iron pipe 21" into the ground to bed rock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

A 9" Ponderosa Pine, scribed "T5S R25E S36 SC BT" on double blazes, bears N40°E, 27.3 feet.

A 8" Ponderosa Pine, scribed "R26E S6 BT" on double blazes, bears S18°E, 26.8 feet.

A 7" Ponderosa Pine, scribed "T6S S6 BT" on double blazes, bears S17°W, 51.9 feet.

A 10" Ponderosa Pine, scribed "T5S R25E S35 SC BT" on double blazes, bears N28° 30'W, 28.1 feet.

The new bearing trees each have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B".

I hereby certify the above corner point was perpetuated as hereon described on April 28, 2003. Magnetic declination set in compass: 19°E.

NAD '83 UTM Zone 11 position: 4995425N 290830E (plus or minus two meters).


REGISTERED
PROFESSIONAL
LAND SURVEYOR
DENNIS L. GAWLORD
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY
Morrow County Surveyor

Date: 1-4-14

Rec'd By: S.K.H

No.: 5525721

Folder No.: _____