

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 23  
DIAGRAM



History of original corner establishment:

The original corner, on the first standard parallel south, was established by Everett A. Thatcher on August 13, 1879, under GLO contract No. 325, as follows:

Set a stone, 15" x 13" x 5", for 1/4 section corner.  
Raised a mound of stone at corner.

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 16" x 11" x 6" and has faint chisel marks on one face, from which:

An original, unrecorded, large, badly decayed Ponderosa Pine snag, 4 feet high, with scribes, "1/4 S SC BT", visible on double blazes, bears N21° 30' E, 24.5 feet.

Monument and accessories established to perpetuate the original position of this corner:

At the position occupied by the original corner stone, I set a 1" x 30" galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone to the west side of the pipe and build a mound of stones around the pipe, from which:

A 9" Ponderosa Pine, scribed "1/4 S36 SC BT" on double blazes, bears N39° 30' E, 27.2 feet.

A 12" Ponderosa Pine, scribed "R25E BT" on double blazes, bears S40°E, 10.5 feet.

A 10" Ponderosa Pine, scribed "T6S BT" on double blazes, bears S61° 30' W, 38.6 feet.

A 10" Ponderosa Pine, scribed "1/4 S36 SC BT" on double blazes, bears N10°W, 31.3 feet.

The closing corner for sections 5 and 6, T6S, R26E, bears East, 28.6 feet.

The new bearing trees have a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

I hereby certify the above corner point was perpetuated as hereon described on May 16, 2003. Magnetic declination set in compass: 17°E.

NAD '83 UTM Zone 11 position: 4995399N 291623E (plus or minus two meters).

*Dennis L. Gaylor*



Renews June 30, 2003

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

**RECEIVED BY**  
Morrow County Surveyor

Date: 1-04-2014  
Rec'd By: S.K.H.  
No.: 5525223  
Folder No.: \_\_\_\_\_