


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T55, R26E



History of original corner establishment:
 E.A. Thatcher, under G.L.O. contract number 325, dated June 4, 1879, set a stone 12"X 12"X 4" from which:

- A Tamarack, 15" dia., N130°W, 44 lks.
- A Pine, 4" dia., N55°E, 42 lks.
- A Yellow Pine, 36" dia., S20°E, 22 lks.
- A Tamarack, 33" dia., S46°W, 44 lks.

Description of corner evidence found:

- From the corner point located at record distance from original Tamarack stumps:
 - A Tamarack stump with one side rotted off and axe work visible on side facing corner bears S65°W, 29.0 ft.
 - A Tamarack stump, 20" dia., N11½°W, 29.0 ft. with fragmentary scribing.
 - A Ponderosa Pine, down and badly rotted, with scribing visible. This presently bears N46°E, 29 ft. I was unable to determine the original location.
 - A root hole, S20°E, 15 ft.
- I did not find the original corner stone.

Description of monument and accessories I established to perpetuate the original location of this corner:

- At the original corner point I set a 2½"X 30" alum. pipe with a 3" alum. cap containing a magnet and marked:
 - I built a stone mound around the monument.
 - From the corner:
 - A Douglas Fir, 15" dia., N49°E, 71.7 ft. marked: T55 R27E S18 BT
 - A Douglas Fir, 16" dia., S52°E, 39.7 ft.; marked: T55 R27E S19 BT
 - A Douglas Fir, 19" dia., S79°W, 33.5 ft.; marked: T55 R26E S24 BT
 - A White Fir, 11" dia., N39 3/4°W, 21.0 ft.; marked: T55 R26E S13 BT

BTs have blaze and a 6" stripe painted red, a BT tag, and an "Attention" sign. New BTs have, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with an "Attention" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 19°E.

June 29, 1986

Office of Supervisor County of Morris
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 31 day of July, 1986 by Michaelle Darko
 David H. Kunklein (COUNTY OFFICIAL) (DEPUTY)

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Angelle Munnis

OREGON
 JULY 13, 1979
 FAYETTE S. MUNRO
 1832

Form R6-7100-57 (9/71)

RECEIVED BY
 Morrow County Surveyor
 Date 7/21/86
 Rec'd By MVD
 No. 825-K