

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 23
DIAGRAM

History of original corner establishment:

The original corner was established by Everett A. Thatcher on August 17, 1879, under GLO contract No. 325, as follows:

Set a stone, 13" x 11" x 5, for the 1/4 section corner to sections 13 and 24, from which:

T5S R26E
1/4 S13
S24
PLS 1636
2004

A 28" fir bears N45° E, 71 links (46.86 feet).

A 14" Tamarack bears S55° W, 32 links (21.12 feet).

Original corner evidence recovered:

Found the original corner stone solidly set protruding 2" above the ground surface. The corner stone is 10" x 9" x 4" and is plainly marked "1/4" on the north face, from which:

A sawn and decayed Douglas-fir stump, no marks remaining, bears N50° E, 46.9 feet.

A decayed Western Larch stump, no marks remaining, bears S52° W, 21.5 feet.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 28" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the northwest side of the pipe, from which:

A 10" White Fir, scribed "1/4 S13 BT", bears N76° E, 17.9 feet.

A 8" Western Larch, scribed "1/4 S24 BT", bears S88° E, 30.7 feet.

A 13" Douglas-fir, scribed "1/4 S24 BT", bears S38° W, 19.1 feet.

A 11" Ponderosa Pine, scribed "1/4 S13 BT", bears N11° 30' W, 70.5 feet.

The bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the base of the lower blaze. The Ponderosa Pine bearing tree has a "Bearing Tree" sign nailed above the blazes.

I hereby certify the above corner point was perpetuated as hereon described on June 9, 2004. Magnetic declination set in compass: 19° E.
NAD '83 UTM Zone 11 position: 4999958N, 301460E (plus or minus two meters).



RECEIVED BY
Morrow County Surveyor

Date: 1-4-14
 Recd By: S.K.H.
 No.: 5526N23
 Folder No.: _____

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on: