

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: R-1

Corner Sections 19 and 30, T.5S., R.26E, W.M. and Sections 24 and 25, T.5S., R.25E., W.M.

Original corner was set by Thatcher under Contract No. 325 dated 1879.
 His record reads:
 Set a basalt stone 12x12x6 in ground for section corner with mound of stone.
 A spring is called 3.8 chains easterly and a 30" fir line tree is called 6.6 chains northerly.

DIAGRAM	
	T5S
	R25E R26E
	S24 S19

	S25 S30
	1995
	PLS 852

Description of corner evidence found:

Found a stone loose on ground 5' northerly of 1/2 circle of stones firmly imbedded in ground. Stone is 12"x12"x6" in dimension with 2 notches on one side, 6 notches on one side, R25 on one face and R26 on the other face.

The remains of a large fir were found 435' north and a point 251' east fell in a wet area. The spring was not now present in the wet area.

Description of monument and accessories I established to perpetuate the original location of this corner:

In the center of the 1/2 circle of stone, I set a 2 1/2" x 30" aluminum pipe with aluminum cap. I buried the stone along side of the pipe. I stamped the cap as shown in the diagram above. I set the following new witness trees:

- A 16" dbh Douglas Fir bears N76°E, 11.4', scribed T55R26E6S19BT.
- A 11" dbh Douglas Fir bears S37°E, 22.5', scribed T55R26E6S30BT.
- A 8" dbh Douglas Fir bears N78°W, 27.2', scribed T55R25E6S24BT.
- A 18" dbh Douglas Fir bears S22°W, 60.1', scribed T55R25E6S25BT.
- A brass washer stamped ORLS 852 and WAL513922 is nailed between the letters B and T on each new tree.

This work was done February 10, 1995.



David L. Haddock



Office of _____, County of Moran
 State of _____, I hereby certify that the within instrument was filed
 in this office for record on the 7 day of Mar, 1995.
 _____ by _____, 1995.
 (COUNTY OFFICIAL) (DEPUTY)