

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R - 21
DIAGRAM



History of original corner establishment:

The original corner was established by Everett A. Thatcher on August 17, 1879, under GLO contract No. 325, as follows:

Set a stone, 18" x 10" x 4", for the corner to sections 23, 24, 25 and 26, from which:

- A 36" pine bears N70° W, 57 links (37.62 feet).
- A 12" fir bears N64° E, 14 links (9.24 feet).
- A 24" pine bears S52° W, 29 links (19.14 feet).
- A 24" pine bears S1° E, 60 links (39.60 feet).

Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 17" x 9" x 6" and is plainly marked with 4 grooves on the north, narrow face. The stone broke into two pieces when removed from the ground. An un-recorded 2" x 36" iron pipe is driven loosely alongside the corner stone, from which:

- A live 24" Ponderosa Pine with full scribes visible on a partially healed blaze bears S54° W, 17.7 feet.
- A badly decayed Ponderosa Pine stump with no remaining marks bears S1° E, 42.8 feet.
- The remains of a decayed fir log with a blazed face showing full scribing. Root hole bears N61° E, 10.0 feet.
- The original bearing tree to the northeast is gone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 24" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone and the recovered iron pipe along the north side of the pipe and build a mound of stones around the pipe to the cap, from which:

- A 15" Ponderosa Pine, scribed "T5S R26E S24 BT", bears N15°E, 15.2 feet.
 - A 9" Douglas-fir, scribed "T5S R26E S25 BT", bears S20°E, 18.5 feet.
 - A 12" Ponderosa Pine, scribed "T5S R26E S23 BT", bears N39° W, 63.6 feet.
- The new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

Thereby certify the above corner point was perpetuated as hereon described on May 9, 2003. Magnetic declination set in compass: 17°E. NAD '83 UTM Zone 11 position: 4998357N 300614E (plus or minus two meters).



Dennis L. Gaylor

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2003

RECEIVED BY
Morrow County Surveyor

Date: 1-04-2014
Recd By: S.K.H.
No.: 5526221
Folder No.: _____