

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: R-5

Corner Sections 19, 20, 29 and 30, T.5S., R.26E, W.M.

DIAGRAM

TSR R26E
S19 S20

S30 S29
1995
PLS 852

Original corner was set by Thatcher under Contract No. 325 dated 1879.
 His record reads:
 Set a basalt stone 10x10x6 in ground for section corner with mound of stone.

Description of corner evidence found:
 Found a recently broken stone 10"x7"x6" in a mound of stone. Notches not readily apparent.

A tree with a line blaze and a 1951 Kinzua cruisers tag denoting this monument as the corner lies 20 feet easterly. Mr. Reitman, an adjoining land owner had also accepted this monument as the corner. The monument was found to be 5239.82' (record 5287.26') easterly of the southwest corner of section 19. There were no other stone mounds in the area.

Description of monument and accessories I established to perpetuate the original location of this corner:

In the center of the mound of stone, I set a 2 1/2" x 30" aluminum pipe with aluminum cap. I buried the stone along side of the pipe. I stamped the cap as shown in the diagram above. I set the following new witness trees:

- A 15" dbh Ponderosa Pine bears N29°E, 23.9', scribed T55R26E S20BT.
- A 12" dbh Ponderosa Pine bears S31°E, 23.0', scribed T55R26E S29BT.
- A 16" dbh Douglas Fir bears N60°W, 31.3', scribed T55R26E S19BT.
- A 14" dbh Ponderosa Pine bears S64°W, 64.7', scribed T55R26E S30BT.
- A brass washer stamped ORLS 852 and WALSI3922 is nailed between the letters B and T on each new tree.

This work was done February 11, 1995.

**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

David L. Haddock

**OREGON
 JULY 12, 1968
 DAVID L. HADDOCK
 852**

Office of _____, County of Morrow
 State of _____, I hereby certify that the within instrument was filed
 in this office for record on the 7 day of MAR, 1995.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)