

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T - 17
DIAGRAM

History of original corner establishment:

The original corner was established by Everett A. Thatcher on August 19, 1879, under GLO contract No. 325, as follows:

Set a stone, 15" x 11" x 5", for the 1/4 section corner to sections 26 and 27, from which:

- A 24" Tamarack bears N60° W, 18 links (11.88 Feet).
- A 36" pine bears S85° E, 33 links (21.78 feet).

T55 R26E
1/4
S27/S26
PLS 1636
2004

Original corner evidence recovered:

The corner stone is gone, likely disturbed by past logging activities. The original pine bearing tree is now a 36" X 20 foot high broken snag. No marks are on this tree (may have been bark scribed). From the corner point, this pine snag bears S85° E, 21.8 feet. The original Tamarack is now a sawn and uprooted Western Larch stump with a healed blaze. I open the blaze to reveal fragmentary reverse scribing on the overgrowth wood. The root hole where the Western Larch once stood bears N60° W, 11.9 feet.

Monument and accessories established to perpetuate the original position of this corner:

At record bearing and distance from the recovered bearing tree evidence, I set a 1" x 30" flared, galvanized iron pipe 28" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 7" Ponderosa Pine, scribed "1/4 S26 BT", bears N45° 30' E, 27.2 feet.
- A 15" Ponderosa Pine, scribed "1/4 S26 BT", bears S43° 30' E, 68.6 feet.
- A 5" Ponderosa Pine, scribed "1/4 S27 BT", bears S72° W, 46.0 feet.
- A 6" Ponderosa Pine, scribed "1/4 S27 BT", bears N86° W, 91.6 feet.

The new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed to the base of the lower blaze. The Ponderosa Pine bearing tree to the southeast has a "Bearing Tree" sign nailed above the blazes.

I hereby certify the above corner point was perpetuated as hereon described on June 9, 2004. Magnetic declination set in compass: 19° E.
NAD '83 UTM Zone 11 position: 4997590N, 298989E (plus or minus two meters).



RECEIVED BY
Morrow County Surveyor
Date: 1-4-2014
Rec'd By: S.K.H.
No.: 5526T17
Folder No.: _____

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on: