

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

---

History of original corner establishment:

Index: Y-3

Quarter corner sections 30 and 31, T.5S., R.26E, W.M.

DIAGRAM

Original corner was set by Thatcher under Contract No. 325 dated 1879.  
 His record reads:  
 Set a basalt stone 13x9x5 in ground for quarter section corner from which:  
 A 26" Pine bears N57°W, 67 links.  
 A 30" Pine bears S40°E, 6 links.  
 A ravine is called 9.5 chains east of the corner.

T5S R26E	S30
1/4-----	S31
	1995
	PLS 852

Description of corner evidence found:

Found a stone 13"x9"x5". Scribing not readily apparent. Chained to a ravine 630' east of the corner. The stumphole of a large pine bears N57°W, 44' from the stone. The remains of the pine from the stumphole were found on the ground nearby with one root still attached in the stumphole. A clearly scribed 1/4 S was visible on the face of the tree which was down to the ground. The remains of another Pine were found S40°E, 4' with no signs of scribing.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the location of the stone, I set a 2 1/2" x 30" aluminum pipe with aluminum cap. I buried the stone along side of the pipe. I stamped the cap as shown in the diagram above. I set the following new witness trees:  
 A 14" dbh Ponderosa Pine bears N26°E, 134.7', scribed 1/4S30BT.  
 A 16" dbh Douglas Fir bears S52°E, 51.1', scribed 1/4S31BT.  
 A 14" dbh Douglas Fir bears N45°W, 83.8', scribed 1/4S30BT.  
 A 9" dbh Douglas Fir bears S51°W, 87.7', scribed 1/4S31BT.  
 A brass washer stamped ORLS 852 and WAL513922 is nailed between the letters B and T on each new tree.  
 A Bearing Tree tag was nailed to the original tree.

This work was done February 9, 1995.



*David L. Haddock*



Office of \_\_\_\_\_, County of Morrow  
 State of \_\_\_\_\_, I hereby certify that the within instrument was filed  
 in this office for record on the 7 day of Mar, 1995.  
 by \_\_\_\_\_, ( COUNTY OFFICIAL )  
 \_\_\_\_\_ ( DEPUTY )