

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

R26E

X-25

**History of original corner establishment:**


The original corner was established in 1879 by Everett A. Thatcher as follows:

Set Fir post 4 ft. long, 4" in diameter for ¼ Sec. Cor.

From which:

A fir 20" in diameter bears N80°W, 22 lks. distance.

A black pine 8" in diameter bears S86°E, 12 lks. distance.



**Description of corner evidence found:**

Original 20" fir BT is now a sawn Douglas-fir log which has previously opened upper blaze and a partly healed lower blaze with scribing visible on both blazes. The sawn stump also has scribes visible on the unhealed lower blaze. The stump has broken off at ground level and rolled down hill. I can very accurately locate where this tree once stood. It bears N80°W, 14.5 ft. from the corner.

**Description of monument and accessories | established to perpetuate the original location of this corner:**

By reference to the only remaining original BT, I set a 2"x32" galvanized iron pipe with a 2½" brass cap attached, 30" into the ground on a very steep north slope. The brass cap is marked:

From which:

A 9" western larch bears N18°30'W, 13.3 ft., scribed

¼ S36 BT, " on a single blaze.

A 14" Douglas-fir bears N76°E, 16.5 ft., scribed


¼ S31 BT, " on a single blaze.

54-3 and 54-4 signs were placed on all bearing trees.

Compass Declination: 20°East  
I hereby certify the above corner location was perpetuated as described on September 27, 1983.

Witness: Susan E. Newstetter

	T55	
R	¼	R
2	S36   S31	2
6	PLS 1636	7
E	1983	E

  
*Dennis L. Gaylord*

Office of.....County..Surveyor.....County of.....Morrow.....  
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
 Morrow County Surveyor  
 Date 12-5-83  
 Rec'd By MLD  
 No. 6494

Form R6-7100-57 (9/71)