

OREGON CORNER RESTORATION FORM

COUNTY: Morrow DATE: 04/19/04

CORNER DESIGNATION: J-13, the Northeast corner of Section 15, Township 5 South, Range 27 East, W.M., Morrow County, Oregon.

PREVIOUS RENEWAL/SURVEYS ETC.: Corner was originally established by Edward W. Sanderson under Contract No. 417, dated August 24, 1881. Record states: Set a basalt stone 21 x 10 x 5 ins. 14 ins. in ground for Cor. to Secs. 9, 10, 15 and 16. Marked with 4 notches on S. and 3 notches on E. edges. From which: A Pine 8 in. dia. bears N. 50° W. 20 lks. dist. marked T.5S. R.27E. Sec. 9 B.T. A Pine 9 in. dia. bears S.60°E. 7 lks dist. marked T.5S.R.27E. Sec. 15. B.T. A Pine 9 in. dia. bears N 50° E. 7 lks. dist. marked T.5S. R.27E. Sec.10 B.T. A Pine 10 in. dia. bears S.40°W. 87 lks. dist. marked T.5S.R.27E.Sec.16 B.T.

MONUMENT AND ACCESSORIES FOUND: The area has been logged and the corner stone is missing. Found rotted root hole for original NE bearing tree with a wood chunk and axe marks visible, bears N 50°E 7 links (4.6 feet). A 18" diameter pine snag, 4 feet high with scribing and axe marks visible on partly healed blaze, bears S 40° W 87 links (57.4 feet). No evidence remains of the SE and NW bearing trees. The corner point was reestablished by measuring holding record distances from the face of blaze of the bearing tree remains.

MONUMENT MARKING DETAIL:

T5S R27E
S9 | S10
S16 | S15
2004
PLS 1106

MONUMENT SET: A corner point determined as described above, set a 2 1/2" brass cap on 1 1/4" x 30" galvanized iron pipe 26" in the ground and surrounded with a mound of earth. Cap is marked as shown in "Monument Marking Detail".

New Accessories:

- A 8" lodgepole pine scribed "T5SR27ES10BT" with a 3/4" brass washer stamped "PLS 1106" nailed to face of blaze bears North 47° East, 26.8 feet.
- A 12" lodgepole pine scribed "T5SR27ES15BT" with a 3/4" brass washer stamped "PLS 1106" nailed to face of blaze South 33 1/2° East, 18.9 feet.
- A 60 penny nail drove into the top center of a pitched up ponderosa pine stump 24" in diameter and cut 12" above ground level bears South 15° West, 32.9 feet.
- A 60 penny nail drove into the top center a pitched up ponderosa pine stump 15" diameter and cut 16" above ground level bears North 54° West, 61.7 feet.

Attached bearing object signs to all bearing trees and accessories except the rotted original NE bearing tree stump.

Set steel fence post with witness sign attached 1 foot North of the new monument.

LOCATION AND COMMENTS: Corner is located on a ridge top about 400 feet West and 400 feet South of an existing road.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, LSIT
Marc Hammerla
VSS27J13

RECEIVED BY
Morrow County Surveyor
Date: 1-08-05
Rec'd By: RVA
No.: D-1404-M
Folder No.: _____



Will. R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106
RENEWS 6-30-06