

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. J-19

History of original corner establishment:

DIAGRAM

This corner was originally established by Edward W. Sanderson in 1881-82 under GLO Contract Number 417. Surveyor General Field Notes state:

T55 R27E
S11

Set post 4 in dia 4 ft long 24 in. in ground for 1/4 Sec. Cor. marked 1/4S on N face.

1/4
S14
1992
PLS 848

from which

A Flr 10" dia bears S25°W, 12 lks. dist. marked 1/4 S BT
A Flr 10" dia bears N40°W, 20 lks. dist. marked 1/4 S BT

Description of Corner Evidence Found:

After extensive search I could not find this corner and have determined it is lost. I search over a hundred foot radius of the proportioned position and nothing was found. The area consists of dead, dying, rotten fir. I believe the post and BT's have long since rotted away. I re-established this corner's position by single proportionment measure.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground.

From which:
White Flr, 12" dia., bears N28°37'W, 39.0 ft., scribed: 1/4 S11 BT
White Flr, 10" dia., bears N25°13'E, 41.7 ft., scribed: 1/4 S11 BT
Douglas Fir, 18" dia., bears S30°51'E, 19.6 ft., scribed: 1/4 S14 BT
White Fir, 14" dia., bears S70°50'W, 20.3 ft., scribed: 1/4 S14 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 4' south and east of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1988
DOUGLAS M. FERGUSON
848

This work was performed by:
Douglas M. Ferguson PLS 848
Witnessed by: D. Mitchell Ferguson
and Rick Saul
April 23, 1992
Refer to Morrow Co. Survey No.: C-937-E

Office of DR I hereby certify that the within instrument was filed in this office for record on the 9 day of July, 1992
County of MORROW
by SG
(COUNTY OFFICIAL) (DEPUTY)