

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. J-23

History of original corner establishment:

DIAGRAM

This corner was originally established by Edward W. Sanderson in 1881-82 under GLO Contract Number 417. Surveyor General Field Notes state:

T55 R27E

S12

1/4

S13

1992

PLS 848

Set a post 4 in. dia 4 ft. long 24 in. in ground for 1/4 Sec. Cor. marked 1/4 S on N. face. from which

A Tamarack 9 in. dia bears N. 34 lks dist. marked 1/4 S BT  
A Fir 8 in. dia. bears S50°W, 33 lks. dist. marked 1/4 S BT

Description of Corner Evidence Found:

After extensive search nothing was found. The search area for this corner falls in the south edge of a clear cut and I believe all evidence has been lost to logging. I re-established this corners position by single proportionment measure.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 20" in the ground and raised a mound of stone around the monument. From which:

Lodgepole Pine, 10" dia., bears N36°55'W, 140.9 ft., scribed: 1/4 S12 BT  
Ponderosa Pine, 28" dia., bears N00°32'W, 155.8 ft., scribed: 1/4 S12 BT  
Western Larch, 10" dia., bears S51°43'E, 38.4 ft., scribed: 1/4 S13 BT  
Western Larch, 12" dia., bears S64°37'W, 81.0 ft., scribed: 1/4 S13 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and property Boundary (54-2) signs 5' east and west of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

OREGON  
JULY 12, 1988  
DONALD M. FERGUSON  
848

This work was performed by:  
Douglas M. Ferguson PLS 848  
Witnessed by: D. Mitchell Ferguson  
and Rick Saul  
April 23, 1992  
Refer to Morrow Co. Survey No.: C-937-E

Office of \_\_\_\_\_ County of MORROW  
State of OR I hereby certify that the within instrument was  
filed in this office for record on the 9 day of JULY, 1992  
by SB  
(COUNTY OFFICIAL) (DEPUTY)