

OREGON CORNER RESTORATION FORM

COUNTY: Morrow DATE: 05/14/04

CORNER DESIGNATION: J-9, The Southeast Corner of Section 8, Township 5 South, Range 27 East, W.M., Morrow County, Oregon.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Edward W. Sanderson under Contract No. 417, dated August 24, 1881. Record states: Set basalt stone 15 x 6 x 6 ins in ground for Cor. to Secs. 8, 9, 16 and 17, marked with 4 notches on S. and E. edges. From which: A Pine 12 in diam. bears S13°W, 217 lks dist. marked T.5S.R.27E.Sec.17. B.T. A Pine 30 in dia bears S.42°E., 219 lks dist marked T.5S. R.27E. Sec. 16 B.T. No other trees within limits, raised mound of stone alongside.

MONUMENT AND ACCESSORIES FOUND: Found original stone with 4 grooves on two sides and "X" marked on top lying loose at SE edge of large stone mound which appears to be an old rock crib with fence remains extending North, South and East. The stone has been uprooted from original position. Found original bearing tree remains as follows: A 30" diameter ponderosa pine stump with bottom of blaze visible bears S 13 1/2° W a distance of 217 links (143.2 feet). A 32" diameter live ponderosa pine with scribing visible on partly healed blaze bears S 44° E a distance of 269 links (177.5 feet). Note: record dimension of 219 links from the live bearing tree is wrong--after evaluation, I determine the correct record dimension is 269 links or 177.5 feet. The corner point was reestablished by using distance-distance intersection from the original bearing tree accessories, measuring from face of blaze.

MONUMENT MARKING DETAIL:

T5S R27E
S8|S9
S17|S16
2004
PLS 1106

MONUMENT SET: At reestablished corner position as described above, we set a 5/8" x 24" iron rebar with 2" aluminum cap, marked as shown in Monument Marking Detail. The rebar is driven 20" into rocky ground and surrounded with a mound of stone. Set original stone on East side of new monument with marks visible.

New Accessories:

- A 9" ponderosa pine scribed "T5SR27ES9BT" with a 3/4" brass washer stamped "PLS 1106" nailed to face of blaze bears N 67° E, 37.2 feet.
 - A 12" ponderosa pine scribed "T5SR27E S16BT" with a 3/4" brass washer stamped "PLS 1106" nailed to face of blaze bears S 37° E, 10.6 feet.
 - An 8" Ponderosa Pine scribed "T5SR27ES17BT" with a 3/4" brass washer stamped "PLS 1106" nailed to face of blaze bears S 68° W, 34.6 feet.
 - An 8" Ponderosa Pine scribed "T5SR27ES8BT" with a 3/4" brass washer stamped "PLS 1106" nailed to face of blaze bears N 32° W, 17.8 feet.
- Attached bearing object signs to each of the bearing trees.

LOCATION AND COMMENTS: Corner is located about 200 feet West of a road. The original bearing tree is visible from the road.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801


COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, LSIT
Marc Hammersla
Morrow County Surveyor

DATE: 1-08-05
RECD BY: RUM
NO.: 0-1404-AA
Folder No.: _____



Wills: R. Wells



Renews 6-30-06