

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. L-17

History of original corner establishment:

DIAGRAM

This corner was originally established by Edward W. Sanderson in 1881-82 under GLO Contract Number 417. Surveyor General Field Notes state:

T5S R27E  
1/4  
S15|S14  
1992  
PLS 848

Set sandstone 15x8x7 in. 10 ins. in ground for 1/4 sec. cor. marked 1/4 on W face from which

A Pine 15 in. dia. bears N75°E, 92 lks. dist. marked 1/4 S BT  
A Pine 28 in. dia. bears W. 21 lks. dist. marked 1/4 S BT

Description of Corner Evidence Found:

Did not find the original corner stone, lost to logging  
Ponderosa Pine, 26" dia., snag, with scribing visible, bears N75°E, 60.72 ft. (Rec: N75°E, 60.72)


Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner position determined for the remaining original bearing tree I set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 18" in the ground and raised a mound of stone around the monument.

From Which:

Ponderosa Pine, 8" dia., bears N46°30'W, 27.0 ft., scribed: 1/4 S15 BT  
Ponderosa Pine, 8" dia., bears N09°30'E, 21.9 ft., scribed: 1/4 S14 BT  
Ponderosa Pine, 8" dia., bears S83°45'E, 32.2 ft., scribed: 1/4 S14 BT  
Ponderosa Pine, 22" dia., bears S10°15'W, 48.8 ft., scribed: 1/4 S15 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' south and east of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red. This work was performed by:



Douglas M. Ferguson PLS 848  
Witnessed by: D. Mitchell Ferguson  
and Rick Saul  
April 22, 1992  
Refer to Morrow Co. Survey No.: C-937-E

Office of DR County of MORROW  
State of OR I hereby certify that the within instrument was  
filed in this office for record on the 9 day of July, 1992  
by SR  
(COUNTY OFFICIAL) (DEPUTY)