

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. L-21

History of original corner establishment:

DIAGRAM

This corner was originally established by Edward W. Sanderson in 1881-82 under GLO Contract Number 417. Surveyor General Field Notes state:

T5S R27E
1/4
S14|S13
1992
PLS 848

Set sandstone 11x10x6 ins. 7 ins. in ground for 1/4 sec. cor. marked 1/4 on W face. from which

A Fir 30" dia. bears S10°E, 18 lks. dist. marked 1/4 S BT
A Fir 8" dia., bears S40°W, 57 lks. dist. marked 1/4 S BT

Description of Corner Evidence Found:

Proportion position for this corner falls 30 ft. north of creek, record 60 ft. north. I search both areas and those in between and find nothing. This area is swampy and all the stones in the area are soft and falling apart. The original stone has either sunk in the swampy ground or the marks have worn off and I can't identify it. I found no trace of the original bearing trees. I have no choice except to determine this corner is lost and re-established it's position by single proportion measurement.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground.
From which:

Douglas Fir, 26" dia., bears N49°36'W, 66.0 ft., scribed: 1/4 S14 BT
White Fir, 14" dia., bears N74°13'E, 58.5 ft., scribed: 1/4 S13 BT
White Fir, 24" dia., bears S62°09'E, 23.6 ft., scribed: 1/4 S13 BT
White Fir, 16" dia., bears S00°48'W, 36.6 ft., scribed: 1/4 S14 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1988
DOUGLAS M. FERGUSON
848

This work was performed by:
Douglas M. Ferguson PLS 848
Witnessed by: D. Mitchell Ferguson
and Rick Saul
APRIL 23, 1992
Refer to Morrow Co. Survey No.: C-937-E

Office of MORROW County of MORROW
State of OR I hereby certify that the within instrument was
filed in this office for record on the 9 day of JULY, 1992
by SB
(COUNTY OFFICIAL) (DEPUTY)