

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. N-13

History of original corner establishment:

DIAGRAM

This corner was originally established by Edward W. Sanderson in 1881-82 under GLO Contract Number 417. Surveyor General Field Notes state:

T5S R27E	S16	S15
S21	S22	
1992		
PLS 848		

Set stone 24x15x6 ins. 18 ins. in ground for Cor. to secs 15,16,21 and 22, marked with 3 notches on S. and 3 notches on E. edges. from which

A Pine 20 in. dia. bears N37°E, 90 lks dist. marked T5S R27E Sec 15 BT
 A Pine 10 in. dia. bears N30°W, 69 lks dist. marked T5S R27E Sec 16 BT
 A Pine 15 in. dia. bears S60°W, 10 lks dist. marked T5S R27E Sec 21 BT
 A Pine 24 in. dia. bears S30°E, 37 lks dist. marked T5S R27E Sec 22 BT

Description of Corner Evidence Found:

Found original stone set in a mound of stone with 3 notches on south face and 3 notches on east face.

From Which:

Ponderosa Pine, high cut stump with full scribing visible on double blazes, bears N32°37'W, 59.02 ft. (Rec: N37°E, 59.4 ft)
 Ponderosa Pine, stump with scribing visible, bears N24°03'E, 42.23 ft. (Rec: N30°W, 45.5 ft)
 Ponderosa Pine, stump with scribing visible, bears S36°52'E, 5.83 ft. (Rec: S30°E, 6.6 ft.)
 Ponderosa Pine, stump with scribing visible, bears S65°47'W, 22.47 ft. (Rec: S60°W, 24.4 ft)

Description of monument and accessories I established to perpetuate the original location of this corner:

I moved the original corner monument aside and set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 22" in the ground, buried the original corner stone on the north side of the monument, and raised a mound of stone around the monument.

From Which:

Ponderosa Pine, 18" dia., bears N57°45'W, 65.3 ft., scribed:T5S R27E S16 BT
 Douglas Fir, 22" dia., bears N10°30'E, 44.3 ft., scribed:T5S R27E S15 BT
 White Fir, 20" dia., bears S48°15'E, 42.4 ft., scribed:T5S R27E S22 BT
 Douglas Fir, 26" dia., bears S62°15'W, 58.2 ft., scribed:T5S R27E S21 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' east and west of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

OREGON
JULY 12, 1858
DOUGLAS M. FERGUSON
848

This work was performed by:
 Douglas M. Ferguson PLS 848
 Witnessed by: D. Mitchell Ferguson
 and Rick Saul
 March 27, 1992
 Refer to Morrow Co. Survey No.:

Office of _____ County of MORROW
 State of OR I hereby certify that the within instrument was
 filed in this office for record on the 9 day of July, 1992
 by SB
 _____ (DEPUTY)