

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. N-17

History of original corner establishment:

This corner was originally established by Edward W. Sanderson in 1881-82 under GLO Contract Number 417. Surveyor General Field Notes state:

Set sandstone 15x6x6 ins. 10 ins. in ground for Cor. to Secs. 14,15,22 and 23 from which

DIAGRAM

T55 R27E	
S15 S14	
S22 S23	
1992	
PLS 848	

- A Tamarack 8 in. dia. bears N45°E, 32 lks. dist. marked
- T55 R27E Sec 14 BT
- A Fir 8 in. dia. bears S65°E, 48 lks. dist. marked
- T55 R27E Sec 23 BT
- A Fir 10 in. dia. bears S50°W, 23 lks. dist. marked
- T55 R27E Sec 22 BT
- A Fir 12 in. dia. bears N80°W, 33 lks. dist. marked
- T55 R27E Sec 15 BT

Description of Corner Evidence Found:

Found original stone with 4 grooves on one face and 2 grooves on another face. Stone tipped over and lying loose. I accept it's position as it fits reasonably well with the recovered bearing tree in terms of distance.

Western Larch, 28" dia, with healed double blazes, bears N37°14'E, 22.7 ft. (Rec: N45°E, 21.12 ft.)

Description of monument and accessories I established to perpetuate the original location of this corner:


I move the original corner stone aside and set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground and buried the original corner stone on the north side of the monument. From Which:

- Douglas Fir, 26" dia., bears N84°15'W, 68.4 ft., scribed: T55 R27E S15 BT
- White Fir, 12" dia., bears S81°15'E, 70.5 ft., scribed: T55 R27E S23 BT
- Western Larch, 28" dia., bears S02°45'W, 56.8 ft., scribed: T55 R27E S22 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 4' north and 7' west of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

This work was performed by:
 Douglas M. Ferguson PLS 848
 Witnessed by: D. Mitchell Ferguson
 and Rick Saul

April 22, 1992
 Refer to Morrow Co. Survey No.: C-937-E



Office of MORROW County of MORROW
 State of OR I hereby certify that the within instrument was
 filed in this office for record on the 9 day of July, 1992
 by SR
 (COUNTY OFFICIAL) (DEPUTY)