

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. 0-3

History of original corner establishment:

DIAGRAM

None. Corner established this survey

T55 R27E

C

N1/16 S19

C

1992

PLS 848

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 24" in the ground.

From Which:

Douglas Fir, 18" dia., bears S72°36'E, 35.3 ft., scribed: C-N 1/16 S19 BT  
Douglas Fir, 10" dia., bears S52°48'W, 37.4 ft., scribed: C-N 1/16 S19 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and east of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 12, 1992  
DOUGLAS M. FERGUSON  
848

This work was performed by:  
Douglas M. Ferguson PLS 848  
Witnessed by: D. Mitchell Ferguson  
and Rick Saul  
April 18, 1992  
Refer to Morrow Co. Survey No.: C-936-E

Office of \_\_\_\_\_ County of MORROW  
State of OR I hereby certify that the within instrument was  
filed in this office for record on the 9 day of JULY, 1992  
by SB  
(COUNTY OFFICIAL) (DEPUTY)