

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. P-6

History of original corner establishment:

None. Corner established this survey.

DIAGRAM

T5S R27E
W 1/16

C—C
S20
1992
PLS 848

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground.
From which:

White Fir, 14" dia., bears N14°54'W, 14.8 ft., scribed: C-W 1/16 S20 BT
White Fir, 16" dia., bears S85°54'E, 43.0 ft., scribed: C-W 1/16 S20 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and west of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1958
DOUGLAS M. FERGUSON
848

This work was performed by:
Douglas M. Ferguson PLS 848
Witnessed by: D. Mitchell Ferguson
and Rick Saul
April 10, 1992
Refer to Morrow Co. Survey No.: C-936-E

Office of OR I hereby certify that the within instrument was
State of OR filed in this office for record on the 9 day of July, 1992
County of MORROW
by SB
(COUNTY OFFICIAL) (DEPUTY)