

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. P-7

History of original corner establishment:

DIAGRAM

None. Corner established this survey.

T5S R27E
C 1/4

S20
1992
PLS 848

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 27" in the ground.

From which:

White Fir, 18" dia., bears N19°24'W, 63.5 ft., scribed: C1/4 S20 BT
Douglas Fir, 20" dia., bears N81°48'E, 60.2 ft., scribed: C1/4 S20 BT
Douglas Fir, 22" dia., bears S27°25'E, 22.5 ft., scribed: C1/4 S20 BT
Douglas Fir, 26" dia., bears S57°47'W, 41.6 ft., scribed: C1/4 S20 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1985
DOUGLAS M. FERGUSON
848

This work was performed by:
Douglas M. Ferguson PLS 848
Witnessed by: D. Mitchell Ferguson
and Rick Saul
April 10, 1992
Refer to Morrow Co. Survey No.: C-936-E

Office of _____ County of MORROW
State of OR I hereby certify that the within instrument was
filed in this office for record on the 9 day of July, 1992
by SB
(COUNTY OFFICIAL) (DEPUTY)