

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. P-9

History of original corner establishment:

DIAGRAM

This corner was originally established by Edward W. Sanderson in 1881-82 under GLO Contract Number 417. Surveyor General Field Notes state:

T55 R27E	
1/4	
S20	S21
1992	
PLS 848	

Set post 4 in. dia. 4 feet long 24 ins. in ground marked 1/4 S on W. face for 1/4 sec.cor. from which  
 A Fir 8 in. dia. bears N40°W, 40 lks dist.  
 marked 1/4 S BT  
 A Black Pine 4 in. dia. bears N60°E, 11 lks. dist.  
 marked 1/4 S BT

Description of Corner Evidence Found:

Three different search areas were determined due to the fact the north line of Section 20 is 306.74 feet shorter than record. This lead to a 2° bearing break from cardinal along the east line of Section 20. To compound the problem the east line of Section 20 is 148.94 feet longer than record. Obviously some type of stubbing was going on in this area.

We extensively searched all three areas, and those in between, which consisted mainly of rotten, dead and dying white fir. I believe all of the evidence has long since rotted away. I declared this corner lost and re-established it's position by single proportion measurement from the previously re-established section corner 1/2 mile to the north and the remonumented section corner (from original evidence) 1/2 mile to the south.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground.

From which:

Douglas Fir,	28" dia.,	bears N09°37'W,	38.4 ft.,	scribed: 1/4 S20 BT
White Fir,	10" dia.,	bears N79°12'E,	37.1 ft.,	scribed: 1/4 S21 BT
White Fir,	20" dia.,	bears S39°10'E,	58.2 ft.,	scribed: 1/4 S21 BT
Lodgepole Pine,	10" dia.,	bears S47°09'W,	50.7 ft.,	scribed: 1/4 S20 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

OREGON  
JULY 12, 1960  
DOUGLAS M. FERGUSON  
848

This work was performed by:  
 Douglas M. Ferguson PLS 848  
 Witnessed by: D. Mitchell Ferguson  
 and Rick Saul  
 April 24, 1992  
 Refer to Morrow Co. Survey No.: C-936-E

Office of \_\_\_\_\_ County of MORROW  
 State of OR I hereby certify that the within instrument was  
 filed in this office for record on the 9 day of July, 1992  
 by SB  
 \_\_\_\_\_ (DEPUTY)