

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. R-3

History of original corner establishment:

DIAGRAM

This corner was originally established by Edward W. Sanderson in 1881-82 under GLO Contract Number 417. Surveyor General Field Notes state:

T55 R27E
S19
1/4
S30
1992
PLS 848

Set sandstone 12x11x6 ins. 8 ins. in ground for 1/4 Sec. Cor. marked 1/4 on N face from which
A Fir 18 in. dia. bears South, 9 lks. dist. marked 1/4 S BT
A Fir 8 in. dia. bears N10°W, 44 lks dist. marked 1/4 S BT

Description of Corner Evidence Found:

Found 12"x11"x6" stone marked 1/4, loosely set. Stone has not been disturbed.

Douglas Fir, down with scribes visible, bears S10°02'W, 29.8 ft., (Rec: south, 5.94 ft.)

Description of monument and accessories I established to perpetuate the original location of this corner:

I moved the original corner stone aside and set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground and buried the original corner stone on the north side of the monument.

From which:

Douglas Fir, 10" dia., bears N89°54'W, 59.1 ft., scribed: 1/4 S19 BT
White Fir, 12" dia., bears N58°21'E, 24.2 ft., scribed: 1/4 S19 BT
White Fir, 12" dia., bears S12°24'E, 29.3 ft., scribed: 1/4 S30 BT
Western Larch, 14" dia., bears S26°36'W, 42.7 ft., scribed: 1/4 S30 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 11, 1948
DOUGLAS M. FERGUSON
848

This work was performed by:
Douglas M. Ferguson PLS 848
Witnessed by: D. Mitchell Ferguson
and Rick Saul
April 24, 1992
Refer to Morrow Co. Survey No.: C-936-E

Office of MORROW County of MORROW
State of OR I hereby certify that the within instrument was
filed in this office for record on the 9 day of July, 1992
by SR (DEPUTY)
(COUNTY OFFICIAL)