

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. R-7

History of original corner establishment:

This corner was originally established by Edward W. Sanderson in 1881-82 under GLO Contract Number 417. Surveyor General Field Notes state:

DIAGRAM

T5S R27E

S320

1/4 \_\_\_\_\_

S29

1992

PLS 848

Marked fir 10 in. dia. for 1/4 Sec. Cor. marked 1/4 S on N face from which  
A fir 9 in. dia. bears N50°W, 10 lks. dist. marked 1/4 S BT  
A fir 7 in. dia. bears S20°E, 11 lks. dist. marked 1/4 S BT

Description of Corner Evidence Found:

Three search areas were determined and extensively searched. The record distance along this section line is 5,295.84 ft, however I found the distance to be 5,230.44, a difference of 65.40 ft. Search areas were at record distance from each recovered section corner and at proportionate measure. However nothing was found at these areas or in between. We did open two trees (one dead and one alive) in the hopes we had found the corner tree. However no evidence was found. Again the search areas consist of rotten, dead and dying firs. In addition, it appears a fire went through the area around 100 years ago. I believe the evidence has long since rotted away. I declared this corner lost and re-established it's position by single proportion measurement from the remonumented section corners (from original evidence) 1/2 mile east and west.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 27" in the ground.

From which:

White Fir, 12" dia., bears N44°39'W, 12.5 ft., scribed: 1/4 S20 BT  
Yew, 8" dia., bears N47°06'E, 11.8 ft., scribed: 1/4 S20 BT  
Yew, 7" dia., bears S84°24'E, 23.4 ft., scribed: 1/4 S29 BT  
Douglas Fir, 18" dia., bears S50°21'W, 11.6 ft., scribed: 1/4 S29 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 12, 1923  
DOUGLAS M. FERGUSON  
848

This work was performed by:  
Douglas M. Ferguson PLS 848  
Witnessed by: D. Mitchell Ferguson  
and Rick Saul  
April 24, 1992  
Refer to Morrow Co. Survey No.: C-936-E

Office of \_\_\_\_\_ County of MORROW  
State of OR I hereby certify that the within instrument was  
filed in this office for record on the 9 day of JULY, 1992  
by SB  
(COUNTY OFFICIAL) (DEPUTY)