

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X - 17
DIAGRAM

T5S R25E
1/4
S34 S35
PLS 1636
2003

History of original corner establishment:

The original corner was established by Everett A. Thatcher on August 30, 1879, under joint GLO contract No. 325 , as follows:

Set a stone, 13" x 13" x 11" , for 1/4 section corner. Raised a stone mound at corner.

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 14" x 12" x 9" and is plainly marked "1/4" on one face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 25" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the north side of the pipe and build a mound of stones around the pipe, from which:

A 12" Ponderosa Pine, scribed "1/4 S35 BT", bears N60° 30'E, 38.5 feet.

A 10" Ponderosa Pine, scribed "1/4 S35 BT", bears S25° E, 19.1 feet.

A 8" Ponderosa Pine, scribed "1/4 S34 BT", bears S69° 30' W, 24.4 feet.

A 11" Ponderosa Pine, scribed "1/4 S34 BT" , bears N45° W, 34.3 feet.

A wire fence projecting east and west bears south, 1.7 feet.

The bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

I hereby certify the above corner point was perpetuated as hereon described on May 28, 2003. Magnetic declination set in compass: 17° E.

NAD '83 UTM Zone 11 position: 4996325N 289248E (plus or minus two meters).


Dennis L. Gaylord

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY
Morrow County Surveyor

Date: 1-4-2014

Recd By: S.K.H.

No.: 55 25 X 17

Folder No.: _____