

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X - 21
DIAGRAM



History of original corner establishment:

The original corner was established by Everett A. Thatcher on August 30, 1879, under GLO contract No. 325, as follows:

Set a stone, 15" x 13" x 9", for 1/4 section corner. Raised stone mound at corner.

Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 14" x 11" x 7" and is plainly marked "1/4" on the east face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 25" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe, from which:

- A 10" Juniper, scribed "1/4 S36 BT", bears N30° E, 133.3 feet.
 - A 10" Ponderosa Pine, scribed "1/4 S36 BT", bears S34° E, 91.1 feet.
 - A 5" Juniper, scribed "1/4 S35 BT", bears S4° 30' W, 36.9 feet.
 - A 10" Ponderosa Pine, scribed "1/4 S35 BT", bears N65° W, 7.7 feet.
- Each bearing tree is scribed on double blazes and has a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

I hereby certify the above corner point was perpetuated as hereon described on May 7, 2003. Magnetic declination set in compass: 17° E. NAD '83 UTM Zone 11 position: 4996233N 290859E (plus or minus two meters).

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Dennis L. Gaylord

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY
Morrow County Surveyor

Date: 1-4-2014
Rec'd By: S.K.H.
No.: 5525X21
Folder No.: _____