

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. A-5

DIAGRAM
R28E
56195
T55 R28E
199A
PL9 848

History of original corner establishment:
 Corner originally established in 1891, by Edward W. Sanderson, under General Land Office Contract No. 417. Surveyor General's Notes State: Set a basalt stone 12x12x8 ins. in the ground for cor. to Secs. 5 and 6, T55 R28E marked with 1 notch on W and 5 notches on E and 6 notches on S edges.
 From which:
 A pine 36" dia. bears N15°E., 35 lks. dist; marked T4S R28E S5 BT
 A pine 18" dia. bears S40°E., 24 lks. dist; marked T55 R28E S5 BT
 A pine 20" dia. bears S45°W., 36 lks. dist. marked T55 R28E S6 BT
 In 1938 Leonard Carter, Cadastral Engineer for the "General Land Office" performed a Dependent Resurvey; those Notes State: Proportional measure set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground; for cor. secs. 5&6, with brass cap stamped: (see below, Evidence Found) From which: Pine 32" Br. S46°E., 78 lks. mtd. T55 R28E S5 BT, Fir 13" Br. S42°E., 14 lks mtd. T55 R28E S5 BT
Description of corner evidence found:

Found a 2" iron pipe, bent over flat to the ground with a 2-1/2" brass cap stamped as shown Rt. T4S R28E


 56195
 T55 R28E
 1938

Found a Fir 24" dia., live in good condition, with blaze healed over bears S42° 7.7 ft., (Record S42W., 9.2 ft.,)
 Accepted position where pipe goes vertical into the ground, as the section corner position. This position is on line between the Cor. to Sec. 31/32 and the South 1/4 corner of Section 32, T.45., R.28E., and is at record, 299.32 ft. Easterly from the said corner to Sections 31/32.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 2-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 16" in the ground, and raised a mound of stone and earth around the pipe. Placed original pipe on stone mound.
 From which:

Re scribed original bearing tree, as described above. scribed: T55 R28E S6 BT New bearing tree, A Fir 19" dia. bears, S22E, 53.7 ft., scribed: T55 R28E S5 BT Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.
 Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning sign, South 3 ft. from the corner.

RECEIVED
 PROFESSIONAL
 LAND SURVEYOR

 OFFICER
 JULY 12, 1984
 DOUGLAS M. FERGUSON
 848

RECEIVED BY
 Morrow County Surveyor
 File 1-10-86
 LUDWIG MILD
 235-K

Work by D.M. Ferguson, PLS 848, Mt. Vernon Ora.
 On Aug. 9, 1984
 Witnessed by J. David Brinton, PLS 2065

Office of SURVEYOR County of MORROW
 State of OREGON I hereby certify that the within instrument was filed in this office for record on the 11th day of September, 1985
David K. Krambein by David Reynolds
 (COUNTY OFFICIAL) (DEPUTY)