

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX NO. A-9

History of original corner establishment:
Corner originally established in 1891, by
Edward W. Sanderson, under General Land Office
Contract No. 417. Surveyor General's Notes
State: (See official GLO Notes)

DIAGRAM
R28E
BY
S33

S51S4
T5S R28E
1938
GLO

In 1938 Leonard Carter, Cadastral Engineer for the "General Land Office" performed a Dependent Resurvey, Those Notes State: Proportional measure set an iron post, 3 ft. long, 2 ins. diam., 14 ins. in the ground, to bedrock and in a mound of stone to top, for cor. of sec. 4 and 5 only, with brass cap mkd. (See **DIAGRAM**) From which:
A Douglas fir, 6 ins. diam., bears S59°E., 56 lks. dist., mkd. T5S R28E S4 BT
A Douglas fir, 13 ins. diam., bears S38°W., 53 lks. dist., mkd. T5S R28E S5 BT
Description of corner evidence found:

Found 2" iron pipe with 2-1/2" brass cap stamped
as shown on the **DIAGRAM**

Found section 4 bearing tree, as taken in 1938
resurvey, a fir 10" dia. bears Record S59°E., 37.0 ft.
Blaze is healed over.

**Description of monument and accessories | established to perpetuate the
original location of this corner:**

Maintained Corner by setting a steel post with warning and boundary signs,
West, 5 ft. from the corner.

Maintained Accessories by nailing Bearing Tree sign above blaze and warning
sign to back of the tree taken by Carter in 1938, and painted a 6" red band
at breast ht. around that tree.

Scribed new Bearing Trees,
A Fir 8" dia. bears, S71°E., 20.5 ft., scribed: T5S R28E S4 BT
A Fir 12" dia. bears, S20°W., 20.0 ft., scribed: T5S R28E S5 BT
Measurements to trees taken with a metal tape and magnetic compass,
with Declination set off 20 deg. East.
Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing
Tree Sign above blaze, and warning sign on back of each tree. Painted
a 6" red band at breast ht. around each tree.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
[Signature]
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.
On Aug. 8, 1984
Witnessed by: J. David Erinton., PLS 2065

Office of... S. WINNEY ¹⁸ County of... WASCO
State of... Ore. I hereby certify that the within instrument was filed in this office
for record on the 10th day of September, 1988
... David H. Krumbein by D. West Rayneley
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Morrow County Surveyor

PLS 1-10-86
D. M. FERGUSON
740-K