

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishments:

Index: B-10

North 1/16 corner sections 3 and 4, T.55S., R.20E., W.M.	
Corner first set by PLS 1638 in 1979.	1 DIAGRAM
PLS record reader Set a 2 1/2" x 30" iron pipe 25" in the ground, with a brass cap marked as shown: (see diagram). From which I scribed RT's.	1 T55 R20E
A Lodge pine 15" in diam, bears N70° W 10.3' marked N 1/16 S4 T55 R20E RT.	1 N1/16 S4 T55
A Lodge pine 15" in diam, bears N85° E 35.6' marked N 1/16 S5 T55 R20E RT.	1 1979
	1 PLS 1638
	1
	1

Description of corner evidence found:

Found the iron pipe as described with brass cap stumped as shown in the diagram. From which:  
 A dead and down 14" dbh Lodgepole Pine bears N71° 48' W, 10.5' with visible scribe. A 14" dbh Lodgepole pine stump 6' high bears N87° 01' E, 29.2' scribed N1/16T55R20E50BT.

Description of monument and accessories I established to perpetuate the original location of this corner:  
 The bearings were based on the surveyed bearing between the witness corner and the N 1/16 corner of sections 3 and 4 as recorded by PLS 1638 in Morrow County survey 265-K. I set the following new witness trees:  
 A 14" dbh White Fir bears N48° 02' N, 126.4' scribed N1/16S4BT;  
 A 9" dbh twin white fir bears S81° 27' E, 108.3' scribed N1/16S2BT;  
 An aluminum washer stumped PLS 852 is nailed between the letters B and T on the new trees. All the RT's have LBM and BT signs attached. Painted 3" red bands around all the trees and painted the scribe blades red.

This work was done October 29, 1992.

**REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR**

*David L. Haddock*

**OREGON  
 JULY 12, 1988  
 DAVID L. HADDOCK  
 852**

Office of \_\_\_\_\_ County of \_\_\_\_\_  
 State of \_\_\_\_\_ I hereby certify that the within instrument was filed  
 in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_.  
 \_\_\_\_\_ by \_\_\_\_\_  
 ( COUNTY OFFICIAL ) ( DEPUTY )