

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: B-15

Center north 1/16 corner section 2, T.55, R.20E, W.1N			
Corner first set by PLS 1638 in 1979,	1	DIAGRAM	1
his record reads: Set a 2 1/2" x 30" iron pipe 24"	1	T59 R20E	1
in the ground, with a brass cap marked as shown: (see	1	C	1
diagram), from which I scribbled BT's:	1	N1/15 1 52	1
A fir 11" in diam. bears N18°W 26.9' marked	1	C	1
ON 1/15 53 BT,	1		1
A pine 10" in diam. bears 914°W 23.0' marked	1	1975	1
ON 1/15 55 BT,	1	PLS 1638	1
	1		1

Description of corner evidence found:
 Found the iron pipe as described with brass cap stamped as shown in the diagram. From which:

- A dead 10" dbh Douglas fir bears N20°19'W, 27.1' with visible scribe.
- A 11" dbh ponderosa pine bears 910°37'W, 23.0' with visible scribe.

Description of monuments and accessories I established to perpetuate the original location of this corner:

The bearings were based on the surveyed bearing between the 1/4 witness corner and the N 1/16 corner of sections 2 and 4 as recorded by PLS 1638 in Morrow County survey 265-X. I set the following new witness brass:
 A 16" dbh ponderosa pine bears N66°07'E, 53.6' scribbled ON 1/15 53 BT.
 An aluminum washer stamped PLS 552 is nailed between the letters D and T on the new tree. All the BT's have LBM and BT signs attached.
 Painted 5" red bands around all the trees and painted the
 scribe bases red.

This work was done October 29, 1992.

**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

David L. Haddock

**OREGON
 JULY 12, 1969
 DAVID L. HADDOCK
 852**

Office of _____ County of _____
 State of _____ I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____,
 by _____ (COUNTY OFFICIAL) _____ (DEPUTY)

Form 86-7100-57 (9/71)