

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: C-19

Quarter corner sections 3 and 4, T.5S., R.20E., W.M.

Original survey of township by Sanderson in 1891.	1	DIAGRAM	1
His record reads: See 18x26 sandstone from which:	1		1
A 8" lodgepole pine bears N55°E, 10 lks.	1	1/4	1
A 6" lodgepole pine bears N55°E, 10 lks.	1	1	1
A 6" lodgepole pine bears S75°W, 15 lks.	1	84 1/89	1
	1	1	1
	1	MC	1
	1	1899	1

Township retraced by Carter of GLO in 1908.
His record reads:

Found 1x1x9 basalt stone in road at 99.17 chains.	1		1
At 98.92 chains, set an iron post 3 ft. long, 1 in.	1		1
diam. for witness corner marked: (see diagram). From which:	1		1
A 22" lodgepole pine bears S65°E, 150 lks. MKD, MC 1/4 S3 ET.	1		1
A 15" lodgepole pine bears N70°N, 59 lks. MKD, MC 1/4 S4 ET.	1		1

Description of corner evidence found:

Found the iron pipe as described with brass cap stamped as shown in the diagram, from which:
A 24" dbh Lodgepole pine snag bears S55°15'E, 120.1' scried MC1/4S3BT;

Description of monument and accessories I established to perpetuate the original location of this corner:

The bearings were based on the surveyed bearing between the witness corner and the N 1/16 corner of sections 3 and 4 as recorded by PLS 1638 In Morrow County survey 255-K. I set the following new witness trees:
A 18" dbh Engelman Spruce bears S44°29'E, 99.0' scried MC1/4S3BT;
A 9" dbh Lodgepole pine bears N39°25'E, 50.1' scried MC1/4S3BT;
A 8" dbh Lodgepole pine bears N54°25'W, 81.3' scried MC1/4S4BT;
A 6" dbh Lodgepole pine bears S39°39'W, 45.6' scried MC1/4S4BT;
An aluminum washer stamped PLS 852 is nailed between the letters B and T on the new trees. All the trees have LBM and RT signs attached.
Painted 6" red bands around all the trees and painted the
scribe bases red.

This work was done October 29, 1992.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

David L. Haddock

**OREGON
JULY 12, 1968
DAVID L. HADDOCK
852**

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____.

(COUNTY OFFICIAL) BY _____ (DEPUTY)

Form RS-7100-57 (9/73)