

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: D-12

South East 1/16 cor. sec. 4 & 5, T.5S., R.22E., W.M.			
Original survey of township by Sanderson in 1881.	1	DIAGRAM	1
This corner not set.	1	T5S R22E	1
Township retraced by Carter of GLO in 1938.	1	SE1/16 S4	1
This corner not set.	1	1979	1
	1	PLS 1638	1

This corner was set by PLS 1638 in 1979.
His record reads:

I set the monument described below at the intersection of the position computed four 1/16 corners of Section 4. At the position described above, I set a 2 1/2" x 30" iron pipe 24" in the ground, with a brass cap marked as shown (see diagram) from which I scribbled BT's;
A lodgepole pine 11" in diam. bears N85°E 11.4' marked SE1/16S4BT.
A lodgepole pine 10" in diam. bears S54°W 9.3' marked SE1/16S4BT.

Description of corner evidence found:
Found the iron pipe as described with brass cap stamped as shown in the diagram. From which:
A 11" dbh lodgepole pine snag bears S85°32'E, 11.4' scribbled SE1/16S4BT;
A 10" dbh lodgepole pine stump bears S52°34'W, 9.3' scribbled SE1/16S4BT;

Description of monument and accessories I established to perpetuate the original location of this corner:
The bearings were based on the surveyed bearing between the SN corner and the South 1/4 corner of section 4 as recorded in by PLS 1638 in Morrow County survey 267-K. I set the following new witness trees:
A 11" dbh Engelman Spruce bears S16°13'E, 71.5' scribbled SE1/16S4BT;
A 11" dbh Lodgepole pine bears N53°05'W, 47.3' scribbled SE1/16S4BT;
An aluminum washer stamped PLS 852 is nailed between the letters B and T on the new trees. All the BT's have L&M and BT signs attached.
Painted 6" red bands around all the trees and painted the scribs diagon red.

This work was done September 24, 1992.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David L. Haddock

OREGON
JULY 12, 1968
DAVID L. HADDOCK
852

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____,
(COUNTY OFFICIAL) by _____ (DEPUTY)

Form RS-7100-57 (9/71)

RECEIVED BY
Morrow County Surveyor
Date 11/92
Rec'd By ADL
No. _____