

INDEX No. ~~E-25~~ |
History of original corner establishment:

T55
R225E
DIAGRAM

This corner was originally established by Edward W. Sanderson in 1881 under GLO Contract Number 417. Surveyor General Field Notes state:

Set a sandstone 18x12x8 ins. 12 ins. in ground for Cor to Secs marked 1 notch on N and 5 notches on S edges, 1,6,7 and 12 150 ft. below ridge

S12	S	7
1936		
(GLO BRASS CAP)		

from which
A Pine 30 in. dia. bears N18°E, 25 lks dist. marked T55 R28E S6 BT
A Fir 20 in. dia. bears N20°W, 18 lks. dist. marked T55 R27E S1 BT
A Fir 9 in. dia. bears S27°W, 18 lks. dist. marked T55 R27E S12 BT
A Fir 12 in. dia. bears S52°E, 78 lks. dist. marked T55 R28E S7 BT

In 1938-39 Leonard Carter, Public Land Surveyor, conducted a dependent resurvey, under special instructions dated March 23, 1938, Group 228. His record states:
The cor. of secs. 1,6,7, and 12, which is a basalt stone, 18x14x8 ins., firmly set, mkd. with 6 grooves on E and 5 grooves on S face.

At point for corner,
Set an iron post, 3 ft. long, 2 ins. diam., 18 ins. in the ground to bedrock, with the original stone deposited at the base, and in a mound of stone to top, for cor. of secs. 1,6,7, and 12, with brass cap mkd. (SEE DIAGRAM) from which:

A Yellow Pine, 30 ins. diam., bears N12°E, 25 lks. dist., mkd. T55 R28E S6. (Old B.T.)
A Douglas fir, 20 ins. diam., bears S53°E, 73 lks. dist., mkd T55 R28E S7 (Old B.T.)
A Douglas fir, 24 ins. diam., bears N29°W, 17 lks. dist., mkd. T55 R27E S1 BT. (Old B.T.)
A Douglas fir, 28 ins. diam., bears N47°E, 108 lks. dist., mkd. T55 R28E S6 BT (New B.T.)
A Douglas fir, 23 ins. diam., bears S35°E, 83 lks. dist., mkd. T55 R28E S7 BT.
A white fir, 7 ins. diam., bears S36°W, 49 lks. dist., mkd. T55 R27E S12 BT (New B.T.)

Description of Corner Evidence Found:

Found 2" dia. iron post with brass cap marked as shown in DIAGRAM, extending approx. 18" out of the ground in a mound of stone. NOTE: The notes state the cap was stamped 1938 not 1936, perhaps pre-stamped in error.

Douglas Fir, 30" dia., windfall with healed blazes bears N38°43'W, 9.90 ft. (1938 GLO Rec: N29°W, 11.22 ft.)
Ponderosa Pine, 38" dia., with blazes almost healed shut, bears N13°59'E, 15.40 ft. (1938 GLO Rec: N12°E, 16.50 ft.)
Douglas Fir stump, 34" dia, with scribes visible, bears N47°02'E, 70.80 ft. (1938 GLO Rec: N47°E, 71.28 ft.)
Douglas Fir snag, 24" dia., with scribing visible, bears S52°40'E, 48.90 ft. (1938 GLO Rec: S53°E, 48.18 ft.)
Douglas Fir snag, 26" dia., 15' high, bears S35°55'E, 53.90 ft. (1938 GLO Rec: S35°E, 54.78 ft.)

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument. From Which:
Ponderosa Pine, 28" dia., bears N46°15'W, 60.8 ft., scribed:T55 R27E S1 BT
White Fir, 8" dia., bears S79°30'E, 38.6 ft., scribed:T55 R27E S7 BT
Douglas Fir, 26" dia., bears S49°15'W, 241.4 ft., scribed:T55 R27E S12 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' south and east of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

This work was performed by:

PROFESSIONAL
SURVEYOR

Douglas M. Ferguson PLS 848
Witnessed by: D. Mitchell Ferguson
and Rick Sauli
April 1, 1992
Refer to Morrow Co. Survey No.: C-938-E

OREGON
JULY 12, 1926
DOUGLAS M. FERGUSON
OFFICE OF

County of MORROW
I hereby certify that the within instrument was
state of OR filed in this office for record on the 9 day of July, 1992
by SB (DEPUTY)