

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: E-11

Quarter corner secs. 4 & 9, T.5S., R.22E., M.M.		
Original survey of township by Sanderson in 1881.	1	DIAGRAM
His record reads: Set 12x12x9 sandstone for 1/4 corner	1	
iron which:	1	
A 6" lodgpole bears N10°W, 13 1ks.	1	54
A 9" lodgpole bears S25°W, 18 1ks.	1	1/4-----
	1	59
	1	1938

Township retraced by Carter of SLD in 1938.

His record reads:

Set iron post 3 ft. long, 1 in. diam, 27 ins. in the	1	
ground for 1/4 sec. cor., with brass cap dkd. (see diagram)	1	
A 13" lodgpole bears N45°E, 84 1ks.	1	
A 17" lodgpole bears S15°W, 90 1ks.	1	

Description of corner evidence found:

Found the iron post with standard SLD brass cap stamped as shown in the diagram. From which:

A 14" dbh Lodgpole pine, dead & down, bears N44°34'E, 53.8' with scribe.

A 22" Lodgpole pine snag bears S17°34'W, 53.8' with scribe.

Description of monument and accessories I established to perpetuate the original location of this corner:

The bearings were based on the surveyed bearing between the SW corner and the south 1/4 corner of section 4 as recorded in by PLS 1638 in Morrow County survey 267-K. I set the following new witness trees:

A 8" dbh Lodgpole Pine bears N35°37'E, 106.8' scribed 1/4598T;

A 7" dbh Lodgpole Pine bears S22°10'E, 42.7' scribed 1/4598T;

A 5" dbh Lodgpole Pine bears S62°52'W, 310.4' scribed 1/4598T;

A 7" dbh Lodgpole Pine bears N31°57'W, 262.8' scribed 1/4598T;

An aluminum washer stamped PLS 852 is nailed between the letters B and T on the new trees. All the ST's have LSM and ST signs attached.

Painted 6" red bands around all the trees and painted the scribe blades red.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David L. Haddock*

OREGON  
JULY 12, 1938  
DAVID L. HADDOCK  
852

Office of \_\_\_\_\_, County of \_\_\_\_\_, State of \_\_\_\_\_, I hereby certify that the within instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_.

( COUNTY OFFICIAL ) by \_\_\_\_\_ ( DEPUTY )

Form RS-7100-57 (9/71)

RECEIVED BY

Morrow County Surveyor

Date 11/9/82  
Rec'd by LDL  
No. \_\_\_\_\_