

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. E-2

History of original corner establishment:

None. Corner established this survey.

DIAGRAM

T55 R28E

S6

W1/16

S7

1992

PLS 848

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 27" in the ground.

From which:

Ponderosa Pine, 30" dia., bears N11°11'E, 302.6 ft., scribed: W1/16 S6 BT
Ponderosa Pine, 12" dia., bears S55°46'W, 91.9 ft., scribed: W1/16 S7 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' south and west of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1988
DOUGLAS M. FERGUSON
848

This work was performed by:
Douglas M. Ferguson PLS 848
Witnessed by: D. Mitchell Ferguson
and Rick Sauli
April 17, 1992
Refer to Morrow Co. Survey No.: C-938-E

Office of MORROW County of MORROW
State of OR I hereby certify that the within instrument was
filed in this office for record on the 9 day of July, 1992
by SB
(COUNTY OFFICIAL) (DEPUTY)