

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. E-3

History of original corner establishment:

DIAGRAM

This corner was originally established by Edward W. Sanderson in 1882 under GLO Contract Number 417. Surveyor General Field Notes state:

55 R28E
S6
1/4
S7
1992
PLS 848

Set sandstone 18x16x4 ins. 12 ins. in ground for 1/4 Sec. Cor. marked 1/4 on N. face. from which

A Pine 24 in. dia. bears N25°W, 32 lks. dist marked 1/4 S BT
A Pine 18 in. dia. bears S50°W, 40 lks. dist marked 1/4 S BT

In 1938-39 Leonard Carter, Public Land Surveyor, conducted a dependent resurvey, under special instructions dated March 23, 1938, Group 228. His record states:

Proportionate measurement:

Set an iron post, 3 ft. long, 1 in. diam., 28 ins. in the ground, for 1/4 sec. cor., with brass cap mkd.

S6
1/4
S7
1938
From which

A yellow pine, 17 in. diam., bears N45°W., 114 lks. dist., mkd. 1/4 S6 BT
A yellow pine, 16 in. diam., bears S19°W., 43 lks. dist., mkd. 1/4 S7 BT

Description of Corner Evidence Found:

Found GLO brass capped monument bent over and broken. It has apparently been run over by a Cat.

Ponderosa Pine, 28" dia., with scribbing visible, bears N45°34'W, 73.40 ft. (1938 GLO Rec: N45°W, 75.24 ft.)
Ponderosa Pine, 20" dia., snag with scribbing visible, bears S19°11'W, 27.60 ft. (1938 GLO Rec: S19°W, 28.38 ft.)

Description of monument and accessories I established to perpetuate the original location of this corner:

Removed bent and broken GLO monument and replaced with a 2-1/2" x 30" aluminum pipe with 3-1/2" aluminum capped monument, stamped as shown in DIAGRAM, set 20" in ground and raised a mound around new monument. Buried the GLO monument in the mound. From Which:

Douglas Fir, 20" dia., bears N57°30'E, 55.4 ft., scribed: 1/4 S6 BT
Douglas Fir, 16" dia., bears S21°30'E, 40.1 ft., scribed: 1/4 S7 BT
Douglas Fir, 14" dia., bears S48°15'W, 31.8 ft., scribed: 1/4 S7 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' south and east of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1903
DOUGLAS M. FERGUSON
848

This work was performed by:
Douglas M. Ferguson PLS 848
Witnessed by: D. Mitchell Ferguson
and Rick Saul
April 20, 1992
Refer to Morrow Co. Survey No.: C-938-E

Office of OREGON County of MORROW
state of OR I hereby certify that the within instrument was
filed in this office for record on the 9 day of July, 1992
by SB

(COUNTY OFFICIAL) (DEPUTY)