

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R287

INDEX No. G.5-1

History of original corner establishment:

DIAGRAM

This line tree was originally established by Edward W. Sanderson in 1881-82 under GLO Contract Number 417. Surveyor General Field Notes state:

T55  
R27E R28E  
WC

34.00 A Fir 26 in. dia on line

Line Tree

34.25 Cross a brook 5 lks wide bears N50°W, 400 ft. below Cor.

S12 ~~1992~~ S7  
1992  
PLS 848

Description of Corner Evidence Found:

Found the rotted remains of a fir stump approx. 17' south of a creek (Rec: 16.5 ft.) coursing approx N60°W. The tree remains appear to have been in the 22-26" dia. range at one time. There are no other trees in the area that would fit as well. I tied this tree into my traverse and found it fits very well. I accept this stump as the remains of the line tree.

Description of monument and accessories I established to perpetuate the original location of this corner:

At a point 10.0 ft. SOUTH, on line, from the line tree, I set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 27" in the ground for a witness corner for the line tree. The bearing trees are to the line tree stump. From which:

A Douglas Fir, 14" dia., bears S55°45'W, 37.2 ft., scribed: LT S12 BT A Yew, 7" dia., bears S64°30'E, 68.1 ft., scribed: LT S 7 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north and south of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 12, 1992  
DOUGLAS M. FERGUSON  
848

This work was performed by:  
Douglas M. Ferguson PLS 848  
Witnessed by: D. Mitchell Ferguson  
and Rick Sauli  
April 21, 1992  
Refer to Morrow Co. Survey No.: C-938-E

Office of County of MORROW  
State of OR I hereby certify that the within instrument was  
filed in this office for record on the 9 day of July, 1992  
by SB  
(COUNTY OFFICIAL) (DEPUTY)