

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. 9-5

History of original corner establishment:

Corner originally established in 1881, by Edward W. Sanderson, under General Land Office Contract No. 417. Surveyor General's Notes State: (See official GLO Notes)

DIAGRAM
(not on cap)
(TSS R29E)
1/4
1
57.98
1
1938
GLO

In 1938 Leonard Carter, Cadastral Engineer for the "General Land Office" performed a Dependent Resurvey. Those Notes State: Proportionate measure set an iron post, 3 ft. long, 1 in. diam., 29 ins. in the ground, for 1/4 sec. cor., with brass cap mkd. (see **DIAGRAM**) from which:
A tamarack, 22 ins. diam., bears S61°E., 27 lks. dist., 1/4 88 BT
A tamarack, 17 ins. diam., bears N55°W., 42 lks. dist., 1/4 97 BT

Description of corner evidence found:

Found 1" iron pipe with 2" brass cap stamped as shown on the **DIAGRAM**.

From Which:

Found a Tamarack 28" dia., live, in good condition, with blaze healed over, Bears, S61°E., 17.8 ft.,
Found a Tamarack 24" dia., live, in good condition, with blaze healed over, Bears, N55°W., 27.7 ft.,

Description of monument and accessories established to perpetuate the original location of this corner:

Maintained corner by setting a steel fence post with warning sign, 1 ft. North from the corner monument

Maintained accessories by nailing bearing tree signs to the bearing trees found and painting a 6" red band around each tree. Required warning signs are in place on each tree.
Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1988
DOUGLAS M. FERGUSON
848

RECEIVED BY

Jeffrey County Surveyor

1-10-86

Jeff MLD

PLS 929-K

Work by D.M. Ferguson, PLS 849, Mt. Vernon Ore.
On Aug. 16, 1984
Witnessed by J. David Brinton, PLS 2065

Office of Surveyor County of MORROW

State of OREGON I hereby certify that the within instrument was filed in this office
for record on the 16th day of September, 1985

..... David H. Krambein by Brent Ramsey
(COUNTY OFFICIAL) (DEPUTY)