

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. G-5

History of original corner establishment:

DIAGRAM

This corner was originally established by Edward W. Sanderson in 1882 under GLO Contract Number 417. Surveyor General Field Notes state:

T55 R28E

1/4

S71S8

1938

Set sandstone 18x11x6 ins. 12 ins. in ground for 1/4 Sec. Cor. marked 1/4 on W. face from which:

(GLO Brass Cap)

A Fir 18 in. dia. bears N80°W, 16 lks. dist. marked 1/4 S BT  
A Fir 24 in. dia. bears S70°E, 24 lks. dist. marked 1/4 S BT

In 1938-39 Leonard Carter, Public Land Surveyor, conducted a dependent resurvey, under special instructions dated March 23, 1938, Group 228. His record states:

Proportionate measurement,

Set an iron post, 3 ft. long, 1 in. diam., 28 ins. in the ground for 1/4 sec. cor., with brass cap mkd. (SEE DIAGRAM) from which

A tamarack, 22 ins. diam., bears S61°E, 27 lks. dist., mkd. 1/4 S8 BT  
A tamarack, 17 ins. diam., bears N55°W, 42 lks. dist., mkd. 1/4 S7 BT

Description of Corner Evidence Found:

- Found 1" iron pipe with 2-1/2" brass cap stamped as shown in DIAGRAM.
- Western Larch, 24" dia., with healed blaze, bears N55°W, 27.72 ft. (1938 GLO Rec: Same)
- Western Larch, 32" dia., with healed blaze, bears S61°E, 17.82 ft. (1938 GLO Rec: Same)


Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument.

From which:

Western Larch, 24" dia., bears N83°30'E, 28.4 ft., scribed: 1/4 S8 BT  
White Fir, 12" dia., bears S89°15'W, 33.9 ft., scribed: 1/4 S7 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. I previously set a steel fence post with ATTENTION sign (54-4) 1' north of the monument (in 1984) which is still present. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red. This work was performed by:



Douglas M. Ferguson PLS 848  
Witnessed by: D. Mitchell Ferguson  
and Rick Saul  
April 1, 1992  
Refer to Morrow Co. Survey No.: C-938-E

Office of \_\_\_\_\_ County of MORROW  
State of OR I hereby certify that the within instrument was  
filed in this office for record on the 9 day of July, 1992  
by SB  
(COUNTY OFFICIAL) (DEPUTY)