

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. B-7

History of original corner establishment:

Corner not previously established.

<b>DIAGRAM</b>
T55 R29E
C1/4
SB
1984
PLS 948

Description of corner evidence found:

Corner not previously established.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 2-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 26" in the ground.


From Which:

A Fir 10" dia. Bears, N35°W., 26.8 ft., scribed C1/4 SB BT  
 A Fir 20" dia. Bears, S 89°W., 34.0 ft., scribed C1/4 SB BT  
 Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.

Nailed a brass washer stamped PLS 948 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning sign, 1 ft. north from the corner.

RECEIVED BY

County Surveyor  
 No. 1-10-86  
 Recd by MUD  
 No. 227-K



Work by D.M. Ferguson, PLS 948, Mt. Vernon Ore.  
 On Aug. 16, 1984  
 Witnessed by J. David Brinton, PLS 2065

Office of Surveyor ..... County of Wasco.....  
 State of Oregon..... I hereby certify that the within instrument was filed in this office  
 for record on the 10<sup>th</sup> day of September, 1985  
David H. Krumbein by Shirley Reynolds  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)