

INDEX No. J-1  
 History of original corner establishment:

DIAGRAM

This corner was originally established by Edward W. Sanderson in 1881 under GLO Contract Number 417. Surveyor General Field Notes state:

Set a sandstone 12x8x6 ins. 8 ins. in ground for cor to Secs 7,12,13 and 18 marked with 2 notches on north and 4 notches on south from which

|      |      |      |
|------|------|------|
| T55  | R27E | R28E |
| S12  | S 7  |      |
| S13  | S18  |      |
| 1938 |      |      |

(GLO BRASS CAP)

- A Fir 8 in. dia. bears S60°E, 21 lks dist. marked T5S R28E S18 BT
- A Fir 6 in. dia. bears N30°E, 29 lks. dist. marked T5S R28E S7 BT
- A Fir 4 in. dia. bears N65°W, 12 lks. dist. marked T5S R27E S12 BT
- A Fir 4 in. dia. bears S35°W, 50 lks. dist. marked T5S R27E S13 BT

In 1938-39 Leonard Carter, Public Land Surveyor, conducted a dependent resurvey, under special instructions dated March 23, 1938, Group 228. His record states:  
 The cor. of secs. 7,12,13 and 18, which is a sandstone, 14x12x4 ins., loosely set, mkd. with 4 grooves on S. face; no accessories.

- At point for corner,  
 Set an iron post, 3 ft. long, 2 ins. diam., 14 ins. in the ground to bedrock, with the original stone deposited at the base, and in a mound of stone to top, for cor. of secs. 7,12,13 and 18, with brass cap mkd. (SEE DIAGRAM) from which:
- A Tamarack, 27 ins. diam., bears N47½°E, 84 lks. dist., mkd. T5S R28E S7 BT
- A Tamarack, 20 ins. diam., bears S79¾°E, 57 lks. dist., mkd. T5S R28E S18 BT
- A Tamarack, 21 ins. diam., bears S60°W, 49 lks. dist., mkd. T5S R27E S13 BT
- A Douglas fir, 6 ins. diam., bears N20°W, 109 lks. dist., mkd T5S R27E S12 BT

Description of Corner Evidence Found:

Found 2" dia. iron post with brass cap marked as shown in DIAGRAM, extending approx. 14" out of the ground in a mound of stone.  
 Douglas Fir Stump, bears N46°01'E, 54.5 ft. (1938 GLO Rec: Tamarack, N47½°E, 55.44 ft)  
 Tamarack Snag, bears S80°E, 36.10 ft., (1938 GLO Rec: S79¾°E, 37.62 ft)  
 Tamarack Snag, S59°39'W', 31.3 ft., (1938 GLO Rec: S60°W, 32.34 ft.

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument. From Which:

- White Fir, 10" dia., bears N45°15'W, 67.5 ft., scribed: T5S R27E S12 BT
- White Fir, 24" dia., bears N31°30'E, 29.9 ft., scribed: T5S R28E S 7 BT
- White Fir, 16" dia., bears S69°30'E, 59.3 ft., scribed: T5S R28E S18 BT
- White Fir, 18" dia., bears S25°30'W, 62.3 ft., scribed: T5S R27E S13 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and west of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

This work was performed by:  
 Douglas M. Ferguson PLS 848  
 Witnessed by: D. Mitchell Ferguson  
 and Rick Saul  
 April 1, 1992  
 Refer to Morrow Co. Survey No.: C-938-E

OREGON  
 AUG 12, 1859  
 DOUGLAS M. FERGUSON  
 State of OREGON

I hereby certify that the within instrument was filed in this office for record on the 9 day of July, 1992 by SB

(COUNTY OFFICIAL) (DEPUTY)