

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment: Index: J-13

Corner secs. 9, 10, 15 & 16, T.58., R.28E., W.M.
 Original survey of township by Sanderson in 1881. 1 DIAGRAM 1
 His record reads: Set 18x12x10 sandstone for corner 1 1
 from which: 1 T58 R28E 1
 A 12" fir bears N15°E, 65 lks. 1 89 1 S10 1
 A 10" fir bears N35°W, 18 lks. 1 ----- 1
 A 8" lodgepole bears S40°W, 24 lks. 1 S16 1 S15 1
 A 8" lodgepole bears S50°E, 16 lks. 1 1938 1
 Township retraced by Carter of GLO in 1938. 1 1
 His record reads: 1 1
 Set iron pipe 3 ft. long, 2 in. diam. 27 ins. in the 1 ----- 1
 ground for sec. cor., with brass cap mkd: (see diagram)
 A 18" douglas fir bears S55°1/2 E, 51 lks.
 A 5" tamarack bears N9°1/2°W, 34 lks.
 A 12" spruce bears N16°E, 142 lks.
 A 5" tamarack bears S52°W, 39 lks.

Description of corner evidence found:
 Found the iron pipe with standard GLO brass cap stamped as shown in the diagram. From which:
 A 18" dbh Douglas Fir bears S52°22'E, 33.2' with healed blaze.
 A 9" Tamarack bears N9°23'W, 22.1' with healed blaze.
 A 17" Engelman Spruce, dead and down, bears N16°E, 93.7' with healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:
 The bearings were based on the surveyed bearing between the NE corner and the East 1/4 corner of section 16 as recorded in by PLS 1638 in Morrow County survey 269-K. I set the following new witness trees:
 A 11" dbh Tamarack bears N71°46'E, 20.7' scribed T58R28E310BT;
 A 18" dbh Tamarack bears S74°13'W, 53.8' scribed T58R28E316BT;
 An aluminum washer stamped RLS 852 is nailed between the letters B and T on the new trees. All the BT's have LBM and BT signs attached. Painted 6" red bands around all the trees and painted the scribe blazes red.

This work was done September 23, 1992.



Office of _____ County of _____
 State of _____, I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Morrow County Surveyor
 Date 11/22
 Rec'd By NE
 No. _____