

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-21

History of original corner establishment:

E.W. Sanderson under G.L.O. contract no. 417, dated Aug. 24, 1881, set a basalt stone 18"x 8"x 6", 12" in the ground. From the corner:  
A Black pine, 8" dia., N65°E, 31 lks.  
A Fir, 24" dia., N40°W, 15 lks  
A Fir, 10" dia., S40°E, 46 lks.  
A Fir, 10" dia., S30°W, 30 lks.

Leonard Carter, Public Land Surveyor, under G.L.O. special instructions, Group No. 228, dated Mar. 23, 1938, found the original stone and replaced it with a 2"x 3/8" iron post with a brass cap:  
From the corner:

A White Fir, 15" dia., S32°E, 46 lks. (Old BT)  
A Tamarack, 17" dia., N77°E, 33 lks. (New BT)  
A White Fir, 7" dia., S83°W, 75 lks. (New BT)  
A Spruce 9" dia., N37°W, 27 lks. (New BT)

Description of corner evidence found:  
A 2" iron pipe with a 2 1/2" brass cap (G.L.O.) marked:

T55 R28E  
S11 | S12  
S14 | S13  
1938

From the corner:

A White Fir, 16" dia., S83°W, 48.7 ft.; with a healed blaze.  
A Spruce stump, N37°W, 17.8 ft.; with a 10" dia. tree with a healed blaze down alongside.  
A Western Larch, 19" dia., N77°E, 21.8 ft.; with a healed blaze.  
A White Fir, 22" dia., S32°E, 30.4 ft.; with a healed blaze.

Description of monument and accessories established to perpetuate the original location of this corner:  
I marked a new BT:

A Spruce, 8" dia., N51°W, 17.7 ft.; marked; T55 R28E S11 BT

BTs have blaze and a 6" band painted red, BT tags and "Land Survey Monument" signs. New BT has, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 20°E.

September 14, 1988

DIAGRAM  
T55 R28E  
S11 | S12  
S14 | S13

RECEIVED BY  
Morrow County Surveyor

Date 11/28  
Rec'd By LOHK  
No. G872K

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
OREGON  
JULY 13, 1979  
FAYETTE S. MUNRO  
1832

Office of..... County of.....

State of..... I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by ..... (DEPUTY)  
(COUNTY OFFICIAL)