

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. J-3

History of original corner establishment:

DIAGRAM

This corner was originally established by Edward W. Sanderson in 1882 under GLO Contract Number 417. Surveyor General Field Notes state:

T5S R28E
S7

Set sandstone 12x12x8 ins. 8 ins. in ground for 1/4 sec. cor. marked 1/4 on N. face from which

S18
1939
(GLO Brass Cap)

A Fir 8 in. dia. bears N. 20 lks dist. marked 1/4 S BT
A Fir-12 in. dia. bears S15°E, 35 lks dist. marked 1/4 S BT

In 1938-39 Leonard Carter, Public Land Surveyor, conducted a dependent resurvey, under special instructions dated March 23, 1938, Group 228. His record states:

Proportionate measurement,
Set an iron post, 3 ft. long, 1 in. diam., 28 ins. l in the ground, for 1/4 sec. cor., with brass cap mkd. (SEE DIAGRAM) from which

A Douglas fir, 17 ins. diam., bears N12°W, 58 lks. dist. mkd. 1/4 S7 BT
A White Fir, 10 ins. diam., bears S14°E, 21 lks. dist. mkd. 1/4 S18 BT

Description of Corner Evidence Found:

Found 1" dia pipe with 2-1/2" brass cap stamped as shown in DIAGRAM, extending approx. 6" out of the ground. Monument is in a E-W fenceline and is in good condition.

Douglas Fir, 34" dia., with healed blaze, bears N11°06'W, 36.4 ft.
(1939 GLO Rec: N11°W, 38.28 ft.)

White Fir, 16" dia., snag with healed blaze, bears S14°05'E, 13.5 ft.,
(1939 GLO Rec: S14°E, 13.86 ft.)

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument.
From which:

White Fir, 8" dia., bears N33°15'E, 57.0 ft., scribed: 1/4 S7 BT
Douglas Fir, 28" dia., bears S67°45'E, 37.5 ft., scribed: 1/4 S18 BT
Douglas Fir, 20" dia., bears S41°30'W, 36.7 ft., scribed: 1/4 S18 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument. Nailed a brass washer stamped PLS 848 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs and painted blaze red.



OREGON
JULY 12, 1906
DOUGLAS M. FERGUSON
848

This work was performed by:
Douglas M. Ferguson PLS 848
Witnessed by: D. Mitchell Ferguson
and Rick Saul
April 1, 1992
Refer to Morrow Co. Survey No.: C-938-E

Office of OR I hereby certify that the within instrument was
State of OR filed in this office for record on the 9 day of July, 1992
County of MORROW
by SB
(COUNTY OFFICIAL) (DEPUTY)