

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX NO. J-5

**History of original corner establishment:**

Corner originally established in 1891, by Edward W. Sanderson, under General Land Office Contract No. 417. Surveyor General's Notes State: (See those official GLO Notes.)

In 1938 General Land Office Gastrail Engineer for the

performed a Dependent Resurvey, Those Notes State: Proportionate measure set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, for cor., secs. 7, 8, 17, & 18, with brass cap stamped:

(See DIAGRAM) From which:

A White fir 15 ins. diam., bears N75°E., 39 lks. mkd. T59 R28E S8 BT

A White fir 12 ins. diam., bears S64°E., 52 lks. mkd. T59 R28E S17 BT

A Lodgepole pine, 7 ins. diam., bears S76°W., 50 lks. mkd. T59 R28E S18 BT

A Lodgepole pine, 7 ins. diam., bears N48°E., 10 lks. mkd. T59 R28E S7 BT

In 1981, Ore Land Surveyor PLS 1024 maintained this corner by scribing a



Found 2" iron pipe with 2-1/2 " brass cap, stamped as shown on the **DIAGRAM**, Set 8" above the ground.

From which:

Found 1938 Sec. 8 Bearing Tree, live in good condition at record measurement.

Found 1938 Sec. 7, 18, & 17 bearing trees, standing and

dead, all at record measurement.

Found the tree as scribed by PLS 1024, in 1981, in sec. 7, a fir, 12" dia. bears record. measure.

**Description of monument and accessories | established to perpetuate the original location of this corner:**

Corner monument is in good condition, no maintenance is required.

Maintained accessories as follows:

Painted a 6" red band around all existing bearing trees, as described above

Scribed new Bearing trees:


A Spruce 6" dia. Bears, S22E., 20.0 ft., scribed: S17 BT

A Spruce 6" dia. Bears, S51W., 16.3 ft., scribed: S18 BT

Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted

a 6" red band at breast ht. around each tree.



Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore  
On Aug. 9, 1984  
Witnessed by J. David Brinton, PLS 2065

Office of Surveyor ..... County of WYVON  
State of Oregon ..... I hereby certify that the within instrument was filed in this office  
for record on the 10<sup>th</sup> day of September, 1985  
..... David H. Krumbein by David H. Reynolds  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECORDED BY  
WYVON COUNTY SURVEYOR  
PLS 1-10-86  
M.L.D.  
751-K