

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. J-7

History of original corner establishment:

Corner originally established in 1881, by Edward W. Sanderson, under General Land Office Contract No. 417, Surveyor General's Notes State: (See official GLO Notes)

DIAGRAM
(not on cap)
(T55 R28E)
SB
1/4-____
S17
1939
GLO

In 1938 Leonard Carter, Cadastral Engineer for the "General Land Office" performed a Dependent Resurvey; those Notes state: Proportional measure set an iron post, 3 ft. long, 1 ins. diam., 28 ins. in the ground, for 1/4 sec. cor., with brass cap stamped: (see DIAGRAM), from which:
A white fir, 10 ins. diam.; bears N65°E., 47 lks. mkd. 1/4 SB BT
A white fir, 10 ins. diam.; bears S26°W., 17 lks. mkd. 1/4 S17 BT
Description of corner evidence found:

Found 1" iron pipe with 2-1/2" brass cap, stamped as shown on the DIAGRAM, set 8" above the ground.


Found both bearing trees as scribed in 1939, live in good condition, with balzes healed over, at record measurement from the monument.

SB BT, A fir, 18" dia. (Record: N65°E., 31.0 ft.)
S17 BT, A fir, 14" dia. (Record: S26°W., 11.2 ft.)

Description of monument and accessories | established to perpetuate the original location of this corner:

The monument is in good condition, no maintenance is required.

Maintained Accessories by painting a 6" red band around each tree. All required signs are in place.



RECEIVED BY
Narrow County Surveyor
Date: 1-10-86
Book: 2, MLD
No. 726-K

Work by D.M. Ferguson, PLS 849, Mt. Vernon Ore.
On Aug. 9, 1984
Witnessed by J. David Brinton, PLS 2065

Office of Surveyor County of Wagon
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 10 day of September, 1985
by David H. Kumbier (COUNTY OFFICIAL)
Raymond J. (DEPUTY)